


DOVER[™] 7248 LH

Always check the website for the most updated specifications: www.americh.com




Tub pictured with optional waste & overflow


Builder Series




Platinum Series



Airbath System II Airbath System III





🗢 ROTARY JET

Luxury Series

Combination (pump and blower location only)


LEGEND: P PUMP B BLOWER 🔵 JET 上 SUCTION 🛛 👹 LIGHT

ON/OFF CONTROL

GRAB BAR — ACCESS PANEL (MINIMUM 16" X 20")

INSTALLATION TIPS

- Install according to Owner's Manual and local codes.
- Airbath III units may be $1\frac{1}{2}$ $2\frac{1}{2}$ higher than stated.
- Any whirlpool or Airbath unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater.



All bathtub dimensions are $\pm 1/2^{\prime\prime}$

DIMENSIONS

72" x 48" x 22" (1829 x 1219 x 559 mm) Whirlpool Operating Gallons = 70 (Liters = 303) Gallon to Overflow = 105 (Liters = 454)

MATERIAL: Acrylic (All Americh Standard Colors)

TUB FLOOR: Non-Textured

UNDERMOUNT: Yes

- Advise Americh when ordering to ensure there are no issues with deck mounted controls.
- · Always take dimensions directly from the unit.

ELECTRICAL REQUIREMENTS

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

OPTIONAL ACCESSORIES

- Chromatherapy*
- Grab Bars: 9" * 14" 16"
- High Density Insulation*
- iBath Sound System
- Inline Heater (whirlpool only)
- Jets: Additional or Rotary*
- Lo Profile Tub Edge
- Ozone System (whirlpool and/or Airbath only)
- Pillow: 12" *- Angle
- Remote Control Upgrade (select series only)
- Serenity Soak (tub only)
- Syllent Pump with Heated Air*
- Thermal Comfort System
- (TCS must be at opposite end if used with VSM)
- Trim Kit Upgrade^{*}
- Vibro Sonic Massage
- (VSM must be at opposite end if used with TCS)
- Waste & Overflow
 - Cable Drive Overflow*
 - Linear Overflow

*Standard on Platinum Series

CODES AND COMPLIANCE

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7

• ANSI A112.19.8 Contact Americh for additional approvals.

