


### Always check our website for the most updated specifications: www.americh.com



35



72" x 48" x 20" deep (1829 x 1219 x 508 mm)

Gallons to Overflow = 92 (Liters = 348)

**ELECTRICAL REQUIREMENTS** 

Whirlpool Operating Gallons = 70 (Liters = 265)

Americh recommends one 20 amp ground fault circuit

interrupter (GFCI) for each power supply provided with

-23/8 Dia.

All bathtub dimensions are  $\pm 1/2$ ".

DIMENSIONS

### **CODES AND COMPLIANCE**

Tub pictured with optional


waste & overflow.

Americh products meet or exceed the following standards:


- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8 ASTM F462-79


Contact Americh for additional approvals.

## **Builder Series**




## Airbath System II





**Luxury Series** 


# Airbath System III



# **Platinum Series**

the bathtub.

#### Combination (pump and blower location only)



GRAB BAR - ACCESS PANEL (MINIMUM 16" x 20")

-						Α	С	CE	SSOR	IES			
Apron	Grab Bars				Pillow				Neck	Tile	Installation		
	9"	14"	16"	Madison	Rail	13"	17"	Angle	Head Support Systems	Massage	Flange	Deck Mount	Undermount
•			•		•	٠		•	•		٠	Yes	Yes
= option is available = standard on Platinum Series = option is not available													ole

#### **INSTALLATION TIPS**

- Install product according to our Owners manual and local codes.
- All units with an Airbath III may be 1 1/2 2 1/2" higher than stated.
- All whirlpool or Airbath<sup>TM</sup> unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater. Always consult your local plumber for recommendations as installations will vary.
- When ordering for undermount installation, always advise Americh to assure there are no issues with deck mounted controls.
- Cut-out dimension: 70" x 46"