




## Always check our website for the most updated specifications: www.americh.com









Tub pictured with optional waste & overflow.

All bathtub dimensions are  $\pm 1/2$ ".

#### CODES AND COMPLIANCE

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8 ASTM F462-79

Contact Americh for additional approvals.


#### **DIMENSIONS**

72" x 48" x 20" deep (1829 x 1219 x 508 mm) Whirlpool Operating Gallons = 70 (Liters = 265) Gallons to Overflow = 92 (Liters = 348)


### **ELECTRICAL REQUIREMENTS**

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.


### **Builder Series**




# **Luxury Series**




**Platinum Series** 








# Airbath System II







	ACCESSORIES													
	Grab Bars				Pillow				Neck	Tile	Installation			
Apron	9"	14"	16"	Madison	Rail	13"	17"	Angle	Head Support Systems	Massage	Flange	Deck Mount	Undermount	
•			•		•	•		•	•		•	Yes	Yes	
				ontion in	ovoilobl	- ctandard on Platinum Sorios				inc	- ontion is not available			

## | = option is available



= option is not available

### **INSTALLATION TIPS**

- Install product according to our Owners manual and local codes.
- All units with an Airbath III may be 1 1/2 2 1/2" higher than stated.
- All whirlpool or Airbath<sup>TM</sup> unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater. Always consult your local plumber for recommendations as installations will vary.
- When ordering for undermount installation, always advise Americh to assure there are no issues with deck mounted controls.
- Cut-out dimension: 70" x 46"