

MERICH

SOL® (ROUND DECK) 7238

Always check the website for the most updated specifications: www.americh.com








Tub pictured with optional waste & overflow

All bathtub dimensions are ± 1/2

Builder Series



DIMENSIONS

72" x 38" x 23" (1829 x 965 x 584 mm) Whirlpool Operating Gallons = 67 (Liters = 254) Gallon to Overflow = 92 (Liters = 348)

MATERIAL: Acrylic (All Americh Standard Colors)


TUB FLOOR: Textured

UNDERMOUNT: No

Platinum Series




Luxury Series




ELECTRICAL REQUIREMENTS

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

Airbath System II Airbath System III































■ GRAB BAR -



—ACCESS PANEL (MINIMUM 16" X 20")

OPTIONAL ACCESSORIES

- Chromatherapy*
- Grab Bars: 9" *
- High Density Insulation*
- iBath Sound System
- Inline Heater (whirlpool only)
- Jets: Additional or Rotary*
- Ozone System (whirlpool and/or Airbath only)
- Pillows: 13" *
- Remote Control Upgrade (select series only)
- Serenity Soak (tub only)
- Syllent Pump with Heated Air*
- Thermal Comfort System (TCS must be at opposite end if used with VSM)
- Trim Kit Upgrade*
- Vibro Sonic Massage (VSM must be at opposite end if used with TCS)
- Waste & Overflow
 - Cable Drive Overflow*
 - Linear Overflow

*Standard on Platinum Series

INSTALLATION TIPS

installations will vary.

- Install according to Owner's Manual and local codes.
- Airbath III units may be 11/2" 21/2" higher than stated.
- Any whirlpool or Airbath® unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater. Always consult your local plumber for recommendations as
- Cut-out dimensions: Americh recommends waiting until the actual unit is received.

CODES AND COMPLIANCE

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8 ASTM F462-79 Contact Americh for additional approvals.

