




# AMERICH®

## TURO™ 6030 RH ADA



### DIMENSIONS

60" x 30" x 18" ( 1524 x 762 x 457 mm)

Whirlpool Operating Gallons = 34 (Liters = 129)

Gallon to Overflow = 59 (Liters = 223)

### MATERIAL

Acrylic (All Americh Standard Colors)

### TUB FLOOR

Non - Textured

### UNDERMOUNT: No

### CODES & COMPLIANCE

Americh products meet or exceed the following standards:


- Underwriters Laboratories (UL)
- Underwriters Laboratories - Canada (cUL)
- Canadian Standards Association - (CSA)
- ANSI Z124.1 • ANSI A112-19.7
- ANSI A112.19.8

Contact Americh for additional approvals.


### STANDARD EQUIPMENT

- Apron
- Molded Tile Flange
- Adjustable feet


## BATHING SYSTEMS




Builder Series




Luxury Series



Platinum Series



Combination  
(pump and blower location only)



Airbath System II

N/A

Airbath System III

## LEGEND



## OPTIONAL ACCESSORIES

- Flat Apron  
Non-Removable
- Chromatherapy\*
- Grab Bars: 9" \* - 14" - 16"
- High Density Insulation\*
- iBath Sound System
- Inline Heater (whirlpool only)
- Jets: Additional or Rotary\*
- Ozone System (whirlpool and/or Airbath only)
- Pillows: 12" \* - Angle
- Remote Control Upgrade (select series only)
- Syllent Pump with Heated Air\*
- Thermal Comfort System (TCS cannot be used with VSM)
- Trim Kit Upgrade\*
- Vibro Sonic Massage (VSM cannot be used with TCS)
- Waste & Overflows Upgrades
  - Cable Drive Waste & Overflow\*
  - PVC Waste & Overflow+
  - Linear Waste & Overflow

## INSTALLATION TIPS

- Install according to Owner's Manual and local codes.
- Airbath III units may be 1½" - 2½" higher than stated.
- Any whirlpool or Airbath® unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater.
- Always consult your local plumber for recommendations as installations will vary.
- The combination of multiple systems and options may require components to stick out and/or be remotely installed in the field.

## ELECTRICAL REQUIREMENTS

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

(\*) Standard on Platinum Series (+) Standard on Luxury Series

Removable panel aprons not available on ADA Models. Some functioning Optional Accessories may not be compatible when combining components, please contact Americh to confirm compatibility

Last Update 04/1/19

Always check the website for the most updated specifications: [Americh.com](http://Americh.com)