



150.2400 | 4-Hole Deck Mounted Roman Tub Filler With Hand Held Shower

SPECIFICATIONS:

- Solid Brass construction includes valves
- Four Hole Installation
- Flow Rate = 7.0 GPM @ 60 PSI
- Hand Shower Flow Rate = 2.0 GPM @ 60 PSI w/ back flow prevention
- Diverter handle controls water flow between spout and hand held

FINISHES :

• Chrome - 150.2400CP

STANDARDS:

• ASME A112.18.1 / CSA B125.1

Legislation Compliance

ZeroDrip Technology



