

Underscore® Rectangle

60" x 30" alcove bath K-1121-R

Features

- Integral lumbar support.
- Slotted overflow allows for deep soaking.
- Integral flange helps prevent water from seeping behind wall and simplifies alcove installation.

Material

- Acrylic.
- Acrylic.

Installation

- Right drain.
- Requires K-7271 or K-7272 Clearflo slotted overflow bath drain (sold separately).
- Alcove.

Required Products/Accessories

K-7271 Brass Slotted Overflow Bath Drain

or

K-7272 PVC Slotted Overflow Bath Drain

Recommended Products/Accessories

K-1491 Bath/Whirlpool Pillow

K-1601 Bath/whirlpool footstop, removable

K-24916 Wireless Music Kit

K-702200-G73 Frameless Sliding Bath Door

K-702200-L Frameless Sliding Bath Door

K-23726 Drain treatment

K-23732 Tub & shower cleaner



ADA

Codes/Standards

CSA B45.5/IAPMO Z124 ASTM E162 ASTM E662 ADA ICC/ANSI A117.1

KOHLER® Plastic Baths and Receptors Lifetime Limited Warranty

See website for detailed warranty information.

Available Colors/Finishes

Color tiles intended for reference only.


Color	Code	Description
	0	White
	96	Biscuit
	NY	Dune
	95	Ice™ Grey
	G9	Sandbar
	K4	Cashmere
	58	Thunder™ Grey
413	7	Black Black™





Underscore® Rectangle

60" x 30" alcove bath K-1121-R



Technical Information

All product dimensions are nominal.

Installation: Three-wall alcove

Right Drain location:

42-7/16" x 20" (1078 mm x 508 mm) Basin area, bottom:

54-5/16" x 24-1/4" (1380 mm x 616 mm) Basin area, top:

Weight: 75 lbs (34 kg)

Minimum floor load: 42 lbs/ft2 (205.1 kg/m2)

15-1/8" (384 mm) Water depth: Water capacity: 59.8 gal (226.4 L) Minimum flat for 1-15/16" (50 mm)

door:

Notes

Measure your actual product for rough-in

Install this product according to the installation instructions.

The hot water supply should be 70% of the capacity of the bath or greater. Installations will

ADA compliant when installed to the specific requirements of these regulations.

